

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT



APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED  
OMB No. 1004-0136  
Expires January 31, 2004

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU-79015
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name N/A
2. Name of Operator Newfield Production Company		7. If Unit or CA Agreement, Name and No. N/A
3a. Address Route #3 Box 3630, Myton UT 84052		8. Lease Name and Well No. Federal 9-28-9-17
3b. Phone No. (include area code) (435) 646-3721		9. API Well No. 43-013-33648
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NE/SE 1942' FSL 810' FEL 584980X 39.999987 At proposed prod. zone 4428020Y -110.064487		10. Field and Pool, or Exploratory <del>Monument Data</del> Undesignated
11. Sec., T., R., M., or Blk. and Survey or Area NE/SE Sec. 28, T9S R17E		12. County or Parish Duchesne
13. State UT		
14. Distance in miles and direction from nearest town or post office* Approximatley 17.5 miles southeast of Myton, Utah	15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) Approx. 810' f/lease, NA' f/unit. Approx. 1222'	16. No. of Acres in lease 1,113.95
17. Spacing Unit dedicated to this well 40 Acres	18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Approx. 1222'	19. Proposed Depth 5635'
20. BLM/BIA Bond No. on file UTB000192	21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5373' GL	22. Approximate date work will start* 3rd Quarter 2007
23. Estimated duration Approximately seven (7) days from spud to rig release.	24. Attachments	

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature 	Name (Printed/Typed) Mandie Crozier	Date 4/30/07
Title Regulatory Specialist		
Approved by (Signature) 	Name (Printed/Typed) BRADLEY G. HILL	Date 05-14-07
Title Off ENVIRONMENTAL MANAGER		

Application approval does not warrant or certify the the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

\*(Instructions on reverse)

Federal Approval of this  
Action is Necessary


RECEIVED

MAY 10 2007


DIV. OF OIL, GAS & MINING

**T9S, R17E, S.L.B.&M.**


**NEWFIELD PRODUCTION COMPANY**



WELL LOCATION, S. PLEASANT VALLEY  
 9-28-9-17, LOCATED AS SHOWN IN THE  
 NE 1/4 SE 1/4 OF SECTION 28, T9S,  
 R17E, S.L.B.&M. DUCHESNE COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS  
 PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS  
 MADE BY ME OR UNDER MY SUPERVISION AND THAT  
 THE SAME ARE TRUE AND CORRECT TO THE BEST OF  
 MY KNOWLEDGE AND BELIEF. No. 189377



◆ = SECTION CORNERS LOCATED

BASIS OF ELEV;  
 U.S.G.S. 7-1/2 min QUAD (MYTON SE)

**S. PLEASANT VALLEY 9-28-9-17**  
 (Surface Location) NAD 83  
 LATITUDE = 40° 00' 00.08"  
 LONGITUDE = 110° 00' 18.30"

**TRI STATE LAND SURVEYING & CONSULTING**  
 180 NORTH VERNAL AVE. - VERNAL, UTAH 84078  
 (435) 781-2501

DATE SURVEYED: 01-23-07	SURVEYED BY: C.M.
DATE DRAWN: 02-01-07	DRAWN BY: T.C.J.
REVISED:	SCALE: 1" = 1000'

NEWFIELD PRODUCTION COMPANY  
FEDERAL #9-28-9-17  
NE/SE SECTION 28, T9S, R17E  
DUCHESNE COUNTY, UTAH

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. GEOLOGIC SURFACE FORMATION:

Uinta formation of Upper Eocene Age

2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

Uinta	0' – 1155'
Green River	1155'
Wasatch	5635'

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:

Green River Formation 1155' – 5635' - Oil

4. PROPOSED CASING PROGRAM

Please refer to the Monument Butte Field Standard Operation Procedure (SOP).

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

Please refer to the Monument Butte Field SOP. See Exhibit "C".

6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

Please refer to the Monument Butte Field SOP.

7. AUXILIARY SAFETY EQUIPMENT TO BE USED:

Please refer to the Monument Butte Field SOP.

8. TESTING, LOGGING AND CORING PROGRAMS:

Please refer to the Monument Butte Field SOP.

9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:

The anticipated maximum bottom hole pressure is 1800 psi. It is not anticipated that abnormal temperatures will be encountered.

10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:

Please refer to the Monument Butte Field SOP.

**NEWFIELD PRODUCTION COMPANY  
FEDERAL #9-28-9-17  
NE/SE SECTION 28, T9S, R17E  
DUCHESNE COUNTY, UTAH**

**ONSHORE ORDER NO. 1**

**MULTI-POINT SURFACE USE & OPERATIONS PLAN**

**1. EXISTING ROADS**

See attached Topographic Map "A"

To reach Newfield Production Company well location site Federal #9-28-9-17 located in the NE 1/4 SE 1/4 Section 28, T9S, R17E, Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.6 miles  $\pm$  to the junction of this highway and UT State Hwy 53; proceed southeasterly along Hwy 53 - 11.7 miles  $\pm$  to it's junction with an existing dirt road to the southwest; proceed southwesterly and then southeasterly - 4.2 miles  $\pm$  to it's junction with the beginning of the proposed access road west; proceed westerly along the proposed access road - 60'  $\pm$  to the proposed well location.

**2. PLANNED ACCESS ROAD**

See Topographic Map "B" for the location of the proposed access road.

**3. LOCATION OF EXISTING WELLS**

Refer to Exhibit "B".

**4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

All permanent surface equipment will be painted Carlsbad Canyon.  
Please refer to the Monument Butte Field Standard Operating Procedure (SOP).

**5. LOCATION AND TYPE OF WATER SUPPLY**

Please refer to the Monument Butte Field SOP. See Exhibit "A".

**6. SOURCE OF CONSTRUCTION MATERIALS**

Please refer to the Monument Butte Field SOP.

**7. METHODS FOR HANDLING WASTE DISPOSAL**

Please refer to the Monument Butte Field SOP.

**8. ANCILLARY FACILITIES**

Please refer to the Monument Butte Field SOP.

9. **WELL SITE LAYOUT**

See attached Location Layout Diagram.

10. **PLANS FOR RESTORATION OF SURFACE**

Please refer to the Monument Butte Field SOP.

11. **SURFACE OWNERSHIP** - Bureau Of Land Management (Proposed location and access roads leading to).

12. **OTHER ADDITIONAL INFORMATION**

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. MOAC Report #07-78, 4/5/07. Paleontological Resource Survey prepared by, Wade E. Miller, 3/9/07. See attached report cover pages, Exhibit "D".

Newfield Production Company requests 60' of disturbed area be granted in Lease UTU-79015 to allow for construction of the planned access road. **Refer to Topographic Map "B"**. For the planned access road a temporary width of 60' will be needed for construction purposes with a permanent width of 30' and a running surface of 18'. The construction phase of the planned access road will last approximately (5) days. The planned access road will be an 18' crown road (9' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%. There will be no culverts required along this access road. There will be barrow ditches and turnouts as needed along this road. There are no fences encountered along this proposed road. There will be no new gates or cattle guards required. All construction material for this access road will be borrowed material accumulated during construction of the access road.

Newfield Production Company requests a 290' ROW in Lease UTU-13905 and 3,450' of disturbed area be granted in Lease UTU-79015 to allow for construction of the proposed surface gas lines. It is proposed that the ROW and disturbed area will temporarily be 50' wide to allow for construction of a 6" gas gathering line, and a 3" poly fuel gas line, with a permanent width of 30' upon completion of the proposed gas lines. The construction phase of the proposed gas lines will last approximately (5) days. Both lines will tie in to the existing pipeline infrastructure. **Refer to Topographic Map "C."** For a ROW plan of development, please refer to the Monument Butte Field SOP.

Newfield Production Company requests a 290' ROW in Lease UTU-13905 and 3,450' of disturbed area be granted in Lease UTU-79015 to allow for construction of the proposed water lines. It is proposed that the ROW and disturbed area will temporarily be 50' wide to allow for construction of a buried 3" steel water injection line and a buried 3" poly water return line, with a permanent width of 30' upon completion of the proposed water return line. The construction phase of the proposed water lines will last approximately (5) days. **Refer to Topographic Map "C."** For a ROW plan of development, please refer to the Monument Butte Field SOP.

**Surface Flow Line**

For all new wells, Newfield Exploration requests that a 30' Right of way be granted to allow for construction of up to a 14" bundled pipe. **Refer to Topographic Map "D"** for the proposed location of the proposed flow line. Flow lines will be tan and will be constructed using the following procedures:

Clearing and Grading: the proposed flow line will be placed on the surface of the ground. As such no grading or clearing will be needed. The flow line will be centered staked every 200 feet prior to the installation. The flow line will be as close to the access road as possible without interfering with the normal road travel, or road maintenance

Installation for portions along existing roads, lengths of pipe will be laid in the barrow ditch, welded together and moved into place. For lines that go cross-country minimal access will be needed only for maintenance purpose. It is in the best interest of Newfield Exploration to avoid wet and saturated ground that would cause ruts greater than 3 inches in depth. Disturbed areas will be reclaimed within 120 days of the end of the installation.

Termination and final restoration: A notice of abandonment will be filed with the BLM for final recommendations regarding surface reclamation. After abandonment the flow line will be removed, and any surface disturbance will be reclaimed according to the standards and specifics set by the BLM.

#### **Water Disposal**

Immediately upon first production, all produced water will be confined to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project.

Water not meeting quality criteria, is disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

#### **Threatened, Endangered, And Other Sensitive Species**

**Mountain Plover:** If new construction or surface disturbing activities are scheduled to occur between May 1 and June 15, detailed surveys of the area within 0.5 mile of the proposed location and within 300 feet of proposed access routes must be conducted to detect the presence of mountain plovers. All surveys must be conducted in accordance with the survey protocols outlined in the most recent USFWS Survey Protocol. Surveys must be completed prior to initiating new construction or surface disturbing activities. No new construction or surface disturbing activities will be allowed between March 15 and August 15 within a 0.5 mile radius of any documented mountain plover nest site.

**Burrowing Owl:** Due to the proximity of the location to active prairie dog towns, there is the potential to encounter nesting burrowing owls between April 1 and August 15. If new construction or surface disturbing activities are scheduled between April 1 and August 15, pre-construction surveys will be conducted to detect the presence of nesting burrowing owls within 0.5 mile of any new construction or surface disturbing activity (see Vernal BLM Field Office Protocol). No new construction or surface disturbing activities will be allowed between April 1 and August 15 within a 0.5 mile radius of any active burrowing owl nest.

#### **Reserve Pit Liner**

A 16 mil liner with felt is required. Please refer to the Monument Butte Field SOP.

#### **Location and Reserve Pit Reclamation**

Please refer to the Monument Butte Field SOP.

The following seed mixture will be used on the topsoil stockpile, to the recontoured surface of the reserve pit, and for final reclamation: (All poundages are in pure live seed)

Shadscale	<i>Atriplex Confertifolia</i>	6 lbs/acre
Galletta Grass	<i>Hilaria Jamesii</i>	6 lbs/acre

#### **Details of the On-Site Inspection**

The proposed Federal #9-28-9-17 was on-sited on 4/19/07. The following were present; Dave Allred (Newfield Production), Chuck MacDonald (Bureau of Land Management), and Brandon McDonald (Bureau of Land Management). Weather conditions were clear and ground cover was 100% open.

13. LESSEE'S OR OPERATORS REPRESENTATIVE AND CERTIFICATION

Representative

Name: Dave Allred  
Address: Route #3 Box 3630  
Myton, UT 84052  
Telephone: (435) 646-3721

Certification

Please be advised that NEWFIELD PRODUCTION COMPANY is considered to be the operator of well #9-28-9-17 NE/SE Section 28, Township 9S, Range 17E: Lease UTU-79015 Duchesne County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by US Specialty Insurance #B001832.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

4/30/07

Date





Mandie Crozier  
Regulatory Specialist  
Newfield Production Company

# NEWFIELD PRODUCTION COMPANY

S. PLEASANT VALLEY 9-28-9-17

Section 28, T9S, R17E, S.L.B.&M.



## REFERENCE POINTS

210' WESTERLY = 5378.6'  
 260' WESTERLY = 5380.5'  
 170' NORTHERLY = 5370.8'  
 220' NORTHERLY = 5370.4'

SURVEYED BY: C.M.

SCALE: 1" = 50'





DRAWN BY: T.C.J.

DATE: 02-01-07

**Tri State** (435) 781-2501  
 Land Surveying, Inc.  
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078



**NEWFIELD PRODUCTION COMPANY**  
**CROSS SECTIONS**  
**S. PLEASANT VALLEY 9-28-9-17**



NOTE:  
 UNLESS OTHERWISE NOTED  
 CUT SLOPES ARE AT 1:1  
 FILL SLOPES ARE AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)				
ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	1,880	1,620	Topsoil is not included in Pad Cut	260
PIT	640	0		640
TOTALS	2,520	1,620	960	900

SURVEYED BY: C.M.

SCALE: 1" = 50'

DRAWN BY: T.C.J.

DATE: 02-01-07

**Tri State** (435) 781-2501  
 Land Surveying, Inc.  
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078


# NEWFIELD PRODUCTION COMPANY

## TYPICAL RIG LAYOUT

### S. PLEASANT VALLEY 9-28-9-17

EXISTING ROAD

PROPOSED ACCESS  
ROAD (Max. 6% Grade)



SURVEYED BY: C.M.

SCALE: 1" = 50'

DRAWN BY: T.C.J.

DATE: 02-01-07

**Tri State**  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078  
(435) 781-2501

# Newfield Production Company


## Proposed Site Facility Diagram

Federal 9-28-9-17

NE/SE Sec. 28, T9S, R17E

Duchesne County, Utah

UTU-79015



### Legend

Emulsion Line	.....
Load Rack	-----
Water Line	-----
Gas Sales	-----
Oil Line	-----

### Production Phase:

- 1) Valves 1, 3, and 4 sealed closed
- 2) Valves 2, 5, and 6 sealed open

### Sales Phase:


- 1) Valves 1, 2, 4, 5, and 6 sealed closed
- 2) Valve 3 open


### Draining Phase:

- 1) Valves 1 and 6 open

Diked Section







**NEWFIELD**  
Exploration Company

**S. Pleasant Valley 9-28-9-17**  
**SEC. 28, T9S, R17E, S.L.B.&M.**



**Tri-State**  
*Land Surveying Inc.*  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1 = 100,000  
DRAWN BY: mw  
DATE: 02-12-2007


**Legend**

Existing Road  
Proposed Access

**TOPOGRAPHIC MAP**

**"A"**





**NEWFIELD**  
Exploration Company

**S. Pleasant Valley 9-28-9-17**  
**SEC. 28, T9S, R17E, S.L.B.&M.**



**Tri-State**  
*Land Surveying Inc.*  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078


**SCALE:** 1" = 2,000'  
**DRAWN BY:** mw  
**DATE:** 02-12-2007

**Legend**

- Existing Road
- Proposed Access

**TOPOGRAPHIC MAP**

**"B"**



**NEWFIELD**  
Exploration Company

**S. Pleasant Valley 9-28-9-17**  
**SEC. 28, T9S, R17E, S.L.B.&M.**



**Tri-State**  
*Land Surveying Inc.*  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: mw

DATE: 02-12-2007


**Legend**

- Roads
- Proposed Gas Line
- Proposed Water Line

TOPOGRAPHIC MAP

**"C"**





**NEWFIELD**  
Exploration Company

**SEC. 28, T9S, R17E, S.L.B.&M.**



**Tri-State**  
*Land Surveying Inc.*  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: mw


DATE: 05-08-2007

**Legend**


- Roads
- Proposed Flow Line Bundle
- Proposed Central Battery

TOPOGRAPHIC MAP

"D"







**S. Pleasant Valley 9-28-9-17  
SEC. 28, T9S, R17E, S.L.B.&M.**



**Tri-State  
Land Surveying Inc.**  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078

**SCALE: 1" = 2,000'**  
**DRAWN BY: mw**  
**DATE: 02-12-2007**

Legend	
<span style="color: red;">●</span>	Location
<span style="border: 1px solid black; border-radius: 50%; width: 10px; height: 10px; display: inline-block;"></span>	One-Mile Radius

Exhibit "B"

# 2-M SYSTEM

Blowout Prevention Equipment Systems




EXHIBIT C

CULTURAL RESOURCE INVENTORY OF  
NEWFIELD EXPLORATION'S BLOCK PARCEL IN  
TOWNSHIP 9 SOUTH, RANGE 17 EAST, SECTION 28  
DUCHESNE COUNTY, UTAH

Exhibit "D"  
1 of 2

By:

Christopher G. Roberts

Prepared For:

Bureau of Land Management  
Vernal Field Office

Prepared Under Contract With:

Newfield Exploration Company  
Rt. 3 Box 3630  
Myton, UT 84052

Prepared By:

Montgomery Archaeological Consultants, Inc.  
P.O. Box 219  
Moab, Utah 84532

MOAC Report No. 07-78

April 5, 2007

United States Department of Interior (FLPMA)  
Permit No. 06-UT-60122

State of Utah Antiquities Project (Survey)  
Permit No. U-07-MQ-0230b

**NEWFIELD EXPLORATION COMPANY**

**PALEONTOLOGICAL SURVEY OF PROPOSED  
PRODUCTION DEVELOPMENT AREAS,  
DUCHESNE COUNTY, UTAH**

NW 1/4, SW 1/4 & SE 1/4, NW 1/4 [4, 5 & 6-25-9-16];  
NE 1/4, NW 1/4, SW 1/4 & SE 1/4, NE 1/4 [1,2,7 & 8-25-9-16];  
NE 1/4, NW 1/4, SW 1/4 & SE 1/4, SE 1/4 [9-10-15-16-25-9-16];  
NE 1/4, SW 1/4, [11-25-9-16], Section 25, T 9 S, R 16 E  
Entire Section 28 T 9 S, R 17 E [1 to 5, 7 to 16-28-9-16]  
(Excluding SE 1/4, NW 1/4 [6-28-9-17])

**REPORT OF SURVEY**

Prepared for:

**Newfield Exploration Company**

Prepared by:

Wade E. Miller  
Consulting Paleontologist  
March 9, 2007

**WORKSHEET**  
**APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 05/10/2007

API NO. ASSIGNED: 43-013-33648

WELL NAME: FEDERAL 9-28-9-17

OPERATOR: NEWFIELD PRODUCTION ( N2695 )

PHONE NUMBER: 435-646-3721

CONTACT: MANDIE CROZIER

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering		
Geology		
Surface		

PROPOSED LOCATION:

NESE 28 090S 170E

SURFACE: 1942 FSL 0810 FEL

BOTTOM: 1942 FSL 0810 FEL

COUNTY: DUCHESNE

LATITUDE: 39.99999 LONGITUDE: -110.0045

UTM SURF EASTINGS: 584980 NORTHINGS: 4428020

FIELD NAME: UNDESIGNATED ( 2 )

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-79015

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: GRRV

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

- ☒ Plat
- ☒ Bond: Fed[1] Ind[] Sta[] Fee[]  
(No. UTB000192 )
- ☒ Potash (Y/N)
- ☒ Oil Shale 190-5 (B) or 190-3 or 190-13
- ☒ Water Permit  
(No. MUNICIPAL )
- ☒ RDCC Review (Y/N)  
(Date: \_\_\_\_\_ )
- ☒ Fee Surf Agreement (Y/N)
- ☒ Intent to Commingle (Y/N)

LOCATION AND SITING:

- R649-2-3.
- Unit: \_\_\_\_\_
- ☒ R649-3-2. General  
Siting: 460 From Qtr/Qtr & 920' Between Wells
- R649-3-3. Exception
- Drilling Unit  
Board Cause No: \_\_\_\_\_  
Eff Date: \_\_\_\_\_  
Siting: \_\_\_\_\_
- R649-3-11. Directional Drill

COMMENTS: \_\_\_\_\_

*Sep, Separate file*

STIPULATIONS: \_\_\_\_\_

*1. Federal Approval*  
*2. Spacing Slip*

# MONUMENT BUTTE FIELD LONE TREE (GR) UNIT

FEDERAL  
16-20-9-17

LONE TREE  
FED 13-21-9-17

LONE TREE  
FED 16-21-9-17

LONE TREE  
FED 13-22-9-17

T9S R17E

JOELYN  
FED 1-27

FEDERAL  
6-28-9-17

FEDERAL  
8-28-9-17

28

FEDERAL  
12-28-9-17

FEDERAL  
11-28-9-17

FEDERAL  
10-28-9-17

FEDERAL  
9-28-9-17

FEDERAL  
13-28-9-17

FEDERAL  
14-28-9-17

FEDERAL  
15-28-9-17

FEDERAL  
16-28-9-17

OPERATOR: NEWFIELD PROD CO (N2695)

SEC: 28 T.9S R.17E

FIELD: UNDESIGNATED (002)

COUNTY: DUCHESNE


SPACING: R649-3-2 / GENERAL SITING

**Field Status**  
 [ ] ABANDONED  
 [ ] ACTIVE  
 [ ] COMBINED  
 [ ] INACTIVE  
 [ ] PROPOSED  
 [ ] STORAGE  
 [ ] TERMINATED

**Unit Status**  
 [ ] EXPLORATORY  
 [ ] GAS STORAGE  
 [ ] NF PP OIL  
 [ ] NF SECONDARY  
 [ ] PENDING  
 [ ] PI OIL  
 [ ] PP GAS  
 [ ] PP GEOTHERML  
 [ ] PP OIL  
 [ ] SECONDARY  
 [ ] TERMINATED

## Wells Status

[ ] GAS INJECTION  
 [ ] GAS STORAGE  
 [ ] LOCATION ABANDONED  
 [ ] NEW LOCATION  
 [ ] PLUGGED & ABANDONED  
 [ ] PRODUCING GAS  
 [ ] PRODUCING OIL  
 [ ] SHUT-IN GAS  
 [ ] SHUT-IN OIL  
 [ ] TEMP. ABANDONED  
 [ ] TEST WELL  
 [ ] WATER INJECTION  
 [ ] WATER SUPPLY  
 [ ] WATER DISPOSAL  
 [ ] DRILLING



*Utah Oil Gas and Mining*



PREPARED BY: DIANA MASON  
DATE: 11-MAY-2007



**State of Utah**

**Department of  
Natural Resources**

MICHAEL R. STYLER  
*Executive Director*

**Division of  
Oil, Gas & Mining**

JOHN R. BAZA  
*Division Director*

JON M. HUNTSMAN, JR.  
*Governor*

GARY R. HERBERT  
*Lieutenant Governor*

May 14, 2007

Newfield Production Company  
Rt. #3, Box 3630  
Myton, UT 84052

Re: Federal 9-28-9-17 Well, 1942' FSL, 810' FEL, NE SE, Sec. 28, T. 9 South,  
R. 17 East, Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-33648.

Sincerely,

Gil Hunt  
Associate Director

pab  
Enclosures

cc: Duchesne County Assessor  
Bureau of Land Management, Vernal Office

Operator: Newfield Production Company

Well Name & Number Federal 9-28-9-17

API Number: 43-013-33648

Lease: UTU-79015

Location: NE SE                      Sec. 28                      T. 9 South                      R. 17 East

### Conditions of Approval

#### 1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

#### 2. Notification Requirements

Notify the Division with 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dustin Doucet at (801) 538-5281 office  
(801) 733-0983 home

#### 3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

#### 4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

#### 5. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.





JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

May 23, 2008

Mandie Crozier  
Newfield Production Co  
Route 3 Box 3630  
Myton, UT 84052

43 013 33648  
Federal 9-28-9-17  
95 17E 28

Re: APDs Rescinded at the request of Newfield Production Company


Dear Ms. Crozier:

Enclosed find the list of APDs that you requested to be rescinded to Newfield Production Company. No drilling activity at these locations has been reported to the division. Therefore, approval to drill these wells is hereby rescinded, effective May 20, 2008.

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject locations.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,

  
Diana Mason  
Environmental Scientist

cc: Well File  
Bureau of Land Management, Vernal

Page 2  
May 23, 2008  
Subject:

Ashley Federal 15-22-9-15  
Federal 7-18-9-18  
Federal 7-28-9-17  
Federal 8-28-9-17  
Federal 9-28-9-17  
Federal 11-28-9-17  
Federal 12-28-9-17  
Federal 13-28-9-17  
Federal 14-33-8-18  
Federal 14-28-9-17  
Federal 15-28-9-17  
Federal 16-28-9-17